KOLAR DIVISION.

The 26th January 1888.

NOTICE

Is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 7th February 1888, for constructing a 1st Class Travellers' Bungalow at Urigam Gold Fields, Bowringpet Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of August 1888.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office between the hours of 1 to 4 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of Work.	Unit of Work.	Quantity.	Rate per Unit.
Earthwork	C. Yd.	272	
Burnt stone in chunam	C. Ft.	11.560	
Burnt brick in chunam	Do	1·54	
Chunam plastering	Sq.	122·40	
Chunam pointing	Do	5·50	
White-washing	Do	193·28	
Color washing	Do	47·49	
Burnt stone slabs	S. Ft.	340	
Cornice with chunam	Rg. Ft.	180	
Bamboo matting	Sq.	11·04	
Chocolate painting	Do	12·24	
Wood oiling	Do	78·60	
Teak wood work	C. Ft.	417	
Honné wood work	Do	99	
Roofing with 2nd class Mangalore tiles with teak wood reepers complete	Sq.	51·74	
Ridging with Mangalore tiles with chunam borders ..	Rg. Ft.	303	
Eave boards	Do	202	
Rough stone in mud	C. Ft.	857	
Flooring with gravel	Sq.	6·91	
Teak wood doors panelled with 4 shutters, $4\frac{1}{2}' \times 7'$ ..	Each	2	
Teak wood doors panelled with double shutters $4\frac{1}{2}' \times 7\frac{1}{2}'$ ..	No.	8	
Do do do $3\frac{1}{2}' \times 6\frac{1}{2}'$ ..	No.	8	
Windows with venetians and glass shutters $3\frac{1}{2}' \times 5'$ ..	No.	6	
Do do do $3' \times 4'$ ..	No.	4	
Ventilators $4' \times 2'$ ..	No.	16	
Do $3\frac{1}{2}' + 2'$ ..	No.	2	
Honné wood doors $3' \times 6'$ ..	No.	2	
Do windows $2' \times 2\frac{1}{2}'$ ..	No.	1	
Roofing with pot tiles and junglewood reepers	Sq.	15·70	
Turring junglewood	L. S.	..	
Clearing site	L. S.	..	
Latrine	L. S.	..	
Plastering with mud	Sq.	38·28	
Flooring with concrete	Do	27·51	
Archwork	C. Ft.	392	

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for the construction of a 1st Class Travellers' Bungalow at Urigam Gold Fields," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Y. SRINIVASA RAO,
Executive Engineer.